



P.O. Box 2215
 Monument, CO 80132
 (719) 687-6568
 tim@sealsandstripes.com

Invoice

Date	Invoice #
7/31/2020	3636
PO #	

Bill To
Z&R - High Forest Ranch

Quantity	Description	Rate	Amount
	With any asphalt overlay, we are dependent upon the sub-base / foundation being stable for the asphalt that is on top to see it's maximum life expectancy. An asphalt overlay removes the top layer of asphalt, but does not include any alteration or improvement to the foundation or base underneath the remaining asphalt. A properly installed asphalt overlay / repaving of the road will greatly improve the longevity of the road. A life expectancy of an asphalt overlay should be from 15-20 years.		
	OVERLAY A - Full Depth		
15,000	4" depth of milling / asphalt removal of the existing asphalt surface in preparation for a new asphalt pavement overlay to be installed.	0.50	7,500.00
15,000	Preparation for new asphalt paving to include: cleaning and removal of all dirt/debris for clean surface, a tack binder application over all existing asphalt to chemically fuse both the old and new layer together permanently.	0.25	3,750.00
15,000	6" minimum compacted new hot mix asphalt installed using a 2017 Leeboy 8500D Professional paver. Our up to date professional equipment ensures a high quality finished product.	3.75	56,250.00
			SUB TOTAL \$ 67,500 ✓
	OVERLAY A 2" depth		
18,000	2" depth of milling / asphalt removal of the existing asphalt surface in preparation for a new asphalt pavement overlay to be installed.	0.25	4,500.00
18,000	Preparation for new asphalt paving to include: cleaning and removal of all dirt/debris for clean surface, a tack binder application over all existing asphalt to chemically fuse both the old and new layer together permanently.	0.25	4,500.00
33,000 GSF			
Thank you for your business!		Total	